

# ADDENDUM No. 1

FOR THE

## GREENFIELD COUNTY WATER DISTRICT McKee Well Drilling Project

May 4, 2022



OWNER:  
Greenfield County Water District  
551 Taft Highway  
Bakersfield, CA 93307  
(661) 831-0989

PREPARED BY:  
QK.  
5080 California Avenue, Suite 220  
Bakersfield, CA 93309  
(661) 616-2600

## **ADDENDUM No. 1**

---

The following additions, deletions, or modifications shall become part of the Contract Documents for this Project:


### **BIDDER QUESTIONS**

- Q1.** Does this bid submittal require a bid bond? We have looked through specification documents and do not see any forms, mention of bid bond, or bid security.
- A1.** A bid bond is not required for this project.
- Q2.** Are Sound walls required?
- A2.** Provide sound attenuation panels between drilling operations and any residence or business within 700-feet of the drilling operations. Sound walls shall be a minimum of 24 feet tall. Payment for sound attenuation panels will be considered included in the various items of work.
- Q3.** Where will well development water be discharged?
- A3.** Well development water will be discharged into the Kern Island Canal through an existing opening in the block wall. Sediment shall be removed from the water prior to being discharged into the canal.
- Q4.** Bid item 15 states "Remove Existing Well Pump for Inspection and Maintenance". Please expand on the requirements of this bid item.
- A4.** Contractor shall inspect existing well pump and motor after it has been removed and provide a report and estimate for all recommended replacements or repairs to the existing well pump and motor. The cost for all work for replacements or repairs will be conducted through a change order.
- Q5.** Can well cuttings be left on site? Specs say dry out and remove.
- A5.** Contractor shall follow the specifications.
- Q6.** Should we include disinfection of the wells themselves post bailing/video
- A6.** Disinfection of the wells is required.
- Q7.** Can the existing well and pump specifications be provided?
- A7.** The following specifications are based on previous repairs.
- 10" x .279 col w/clp
  - Assembled Bowls -6 stage, 12 CLC (400 feet below ground elevation)
  - 1 1/2" shaft couplings
  - 2 1/2" x 1 1/2" Tube and Shaft Assemblies
  - 2 1/2" x 1 1/2" Tube and Bearing Assemblies
  - Motor = 100 HP, 1780 RPM motor, 6215 ZZ Bearings, 7226 BG Bearings

**ADDENDUM No. 1**

---

**NOTE: One copy of this Addendum Number 1 shall be signed by the Contractor and must be submitted with the bid as acknowledgement of receipt and acceptance of this Addendum Number 1.**

Prepared by:  5/4/2022  
Rebekah Godett, P.E. Date  
QK

Accepted by: \_\_\_\_\_ Date  
Contractor (Signature)  
\_\_\_\_\_  
Contractor (Print Name) Title